BRUHAT BANGALORE MAHANAGARA PALIKE

BBMP/2017-18/RD/WORK_INDENT29328

APPROVED SCHEDULE - B

P/BBMP/E-PMT/21/2017-18, Date: 15.02.2018

Improvements of roads, drains and culverts at Kodigehalli and surroundings at Kodigehalli ward no. 8

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of P Vijaya Babu	
				In Figures	In Words
1	14.94	KSRRB M200-13.1. Dismantling of existing structures like culverts, Bridges, retaining walls and other structure comprising of masonry, cement concrete, wood work, steel work, including T&P and scaffolding wherever necessary, sorting the dismantled material, disposal of unserviceble material and stacking the serviceble material with all lifts complete as per specifications. II. By mechanical means, A. Cement concrete Grade M-15 & M-20	Cum	465.0	Rupees Four Hundred Sixty Five Only
2	89.25	Removing and resetting of footpath slab	sqm	132.0	Rupees One Hundred Thirty Two Only
3	638.58	KSRRB M300-1. Earth work excavation by manual means in ordinary soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5m, excavated surface levelled and sides neately dressed, the disposed earth to be levelled neatly after breaking of clods complete as per specification.	Cum	186.0	Rupees One Hundred Eighty Six Only
4	92.38	KSRB 4-1.2: Providing and laying in position plain cement concrete of mix 1:3:6 with OPC cement @ 220kgs, with 40mm and down size graded granite metal coarse aggregates @ 0.892 cum and fine aggregates @ 0.465 cum, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation including cost of all materials, labour, HOM of machinery, curing complete as per specifications.	Cum	5348.0	Rupees Five Thousand Three Hundred Forty Eight Only
5	169.2	Providing laying palin / reinforced cement concrete for Box Drain walls of thicknes 10cm to 20 cm including cenmtering shuttering form work etc. complete as per approved drawiong and design MORTH Specification No. 1500,1700,2200 PCC M 20 Grade upto 0.75 m height using concrete mixture.	Cum	10700.0	Rupees Ten Thousand Seven Hundred Only
6	9.31	KSRB - 4.9.2: Providing TMT steel reinforcement Fe500 for R.C.C work including straightening, cutting, bending, hooking, palcing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining memebrs wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM of machinery complete as per specifications.	Tonne	64243.0	Rupees Sixty Four Thousand Two Hundred Forty Three Only
7	646.65	Providing and fixing RCC Precast cover slab of 100mm thick for drain in cement concrete M20 using graded granite jelly 20mm and down size with steel reinforcement, including form work, lift charges, curing and concrete finished surfaces on both sides etc, complete and as per drawing and the directions of Engineer in-charge.	Sqm	1500.0	Rupees One Thousand Five Hundred Only
8	31.8	Providing and fixing RCC Precast cover slab of 250mm thick for drain in cement concrete M20 using graded granite jelly 20mm and down size with steel reinforcement, including form work, lift charges, curing and concrete finished surfaces on both sides etc, complete and as per drawing and the directions of Engineer in-charge.	Sqm	5111.0	Rupees Five Thousand One Hundred Eleven Only
9	9.58	KSRB 4-1.6: Providing and laying in position plain cement concrete of mix 1:2:4 with cement @ 240kgs, with 20mm and down size graded granite metal coarse aggregates @ 0.878 cum and fine aggregates @ 0.459 cum, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per specifications.	Cum	5767.0	Rupees Five Thousand Seven Hundred Sixty Seven Only

P. Vijaya Babu

Signature of the Contractor

14/1

Executive Engineer
Byarayanapura Division
BBMP, Bangalore - 92

14/01